



Project Master List
Ordered by Project Name

Main Office: 4111 Branch Center Rd, Sacramento, CA 95827

(916) 874-6291 Transportation Design& Landscaping Services
(916) 875-5171 Traffic Engineering & Transportation Operations & Maintenance

Project Name & Locations	Supv. Dist.	Project Description	Project Engineer	Plans Sent to Utilities	Board Approval	Constr Starts	Constr Complete	Contract Amount (\$K)
65th St Expressway at 53rd Ave Signal Project	2	Install new traffic signal at the intersection of 65th St. Expressway and 53rd Ave.	Yinlun Xu	09/25 (A)	Dec-27	Apr-28	Oct-28	\$771
HSIP (State)								
AC Overlay Project 2025 Phase A	1,2,3,4,5	Place conventional asphalt concrete, rubberized asphalt concrete, or slurry seal over the existing pavement; ADA compliant upgrades. Construction activities will include base repair, raising manholes, and grinding existing pavement prior to paving.	Brandon Lew	06/25 (C)	Feb-25	Aug-25	Aug-26	\$20,567
Watt Ave - Roseville Rd to James Wy/A St								
Roseville Rd - Watt Ave to Madison Ave								
Airbase Dr - Watt Ave to Overpass								
PH07B1 (North of Woodside Dr, East of Andrea Blvd, South of Tupelo Dr, West of Citrus Heights City Limits)								
Tarleton Dr Area (North of Hillsdale Blvd, East of and including Crowder Wy, South of Oakhollow Dr, West Of Walerga Rd)								
FR01B Partial (North of 41st Ave, East of 41 St, South of 34th AveWest of 44th St)								
Sunrise Blvd - Winding Way to Sunset Ave								
Grand Island Rd - 6,000 ft north of Grand Island Mansion to SR 160								
River Rd - 4,560 ft south of Twin Cities Rd to 660' S/O Locke Rd								
Ivie Rd Raise Crosswalk (at Archohe Elementary School)								
CM11C (North of El Camino Ave, East of Mission Ave, South of Kenneth Ave, West of Walnut Ave								
Keane Dr - Kipling Dr to East End								
Madison Ave - Hazel Ave to Blue Oak Dr								
Madison Ave - San Juan Ave to Fair Oaks Blvd								
RM03A1 (North of and including Canberra Dr, East of Watt Ave, South of Alderson Ave, West of Thornhill Dr)								
2 DWS on American River Dr & Tenyson Way (Jesuit HS)								

Ghilotti Construction Company, Inc. - #4648
Local, City of Citrus Heights cost share

Project Name & Locations	Supv. Dist.	Project Description	Project Engineer	Plans Sent to Utilities	Board Approval	Constr Starts	Constr Complete	Contract Amount (\$K)
AC Overlay Project 2025 Phase B	3,4,5, RC	Place conventional asphalt concrete, rubberized asphalt concrete, or slurry seal over the existing pavement; ADA compliant upgrades; Bridge Deck Maintenance. Construction activities will include base repair, raising manholes, and grinding existing pavement prior to paving.	Daniel Lockett	05/25 (C)	Feb-25	Aug-25	May-26	\$11,468
FF01B (North of Palm Ave, East of HWY 1-80, South of Leader Ave, West of Garfield Ave)								
Fair Oaks Blvd - Manzanita Ave to Marshall Ave								
FO14C Partial (Hidden Valley Cir, Ranchita Wy, Van Dyce Wy)								
FO08B Partial (Buchannan Dr and Deerwood Ct)								
TC04A (North of El Camino Ave, East of Fulton Ave, South of Marconi Ave, West of Morse Ave)								
Elkhorn Blvd - 18th St to 26th St								
Grant Line Rd - Jackson Rd to Kiefer Blvd								
Bradshaw Rd - Folsom Blvd to Hyannis Wy								
Isleton Rd - 1,100' North of Andrus Island Rd to 3,300' South of Andrus Island Rd								
Granite Construction - #4649								
Twin Cities Rd - Cosumnes River Bridge to Pellandini Rd	General Fund, City of Rancho Cordova cost share							
AC Overlay Project 2026 Phase A	1,3,4	Place conventional asphalt concrete, rubberized asphalt concrete, rubberized cape seal or slurry seal over the existing pavement; ADA compliant upgrades; Replace damaged culverts. Construction activities will include base repair, raising manholes, and grinding existing pavement prior to paving.	Daniel Lockett	01/26 (B)	Jan-26	Jun-26	Nov-26	\$14,000
Elkhorn Blvd - 26th Ave to 32nd St								
Walerga Rd - Don Julio Blvd to Elkhorn Rd								
Madison Ave - Kenneth Ave to Hazel Ave								
Sunrise Blvd - Sunset Ave to Sunrise Ridge Dr								
Oak Ave - Chestnut Ave to Santa Juanita Ave								
Antelope Rd - Walerga Rd to Elverta Rd								
Watt Ave - El Camino Ave to Marconi Ave								
Walerga Rd - Elkhorn Blvd to Antelope Rd								
6411 Grant Ave - Culvert Replacement Only								

Project Name & Locations	Supv. Dist.	Project Description	Project Engineer	Plans Sent to Utilities	Board Approval	Constr Starts	Constr Complete	Contract Amount (\$K)
AC Overlay Project 2026 Phase B	1,2,5, City of Sac, RC	Place conventional asphalt concrete, rubberized asphalt concrete, or slurry seal over the existing pavement; ADA compliant upgrades. Construction activities will include base repair, raising manholes, and grinding existing pavement prior to paving.	Brandon Lew	02/26 (B)	Jan-26	Apr-26	Sep-26	\$18,900
Florin Rd - French Rd to 1,000' e/o Gardner Ave								
47th Ave - Perry Ave to Roosevelt Ave								
48th Ave - Perry Ave to Roosevelt Ave								
Baker Ave - West end to Stockton Blvd								
Scott Rd - Boys Rand Rd to 3 miles north								
Consumnes Rd - Dillard Rd to Wilton Rd								
RM03A2 (North of Jackson Rd, East of Watt Ave, South of Wildrose Wy, West of Thornhill Dr)								
Alta Mesa Rd - Twin Cities Rd to Valinsin (Curve)								
Isleton Rd-5,000 ft s/o Andrus Isl. Rd to Highway 160								
River Rd - 660 ft s/o Locke Rd to 2,000' south								
RM06A (North of Kiefer Blvd, East of Rosemont Dr, South of Rosewood Dr, West of South Port Dr)								
RP01C West (Hyannis Wy [West of Bradshaw Rd], Adirondack Wy, Chad Ct)								
Calvine Rd - Highway 99 to 250' w/o Cliffcrest Dr								
Gerber Rd - French Rd to Elk Grove Florin Rd								
Ione Culvert								
AC Overlay Project 2026 Phase C	3	Place conventional asphalt concrete, rubberized asphalt concrete, or slurry seal over the existing pavement; ADA compliant upgrades; Bridge Deck Maintenance. Construction activities will include base repair, raising manholes, and grinding existing pavement prior to paving. Bridge Maintenance include Polyester Concrete Overlay and concrete deck repair.	Daniel Lockett	03/26 (B)	Jan-26	Jul-26	Nov-26	\$5,800
Greenback Ln - Hwy I80 to CH City Limits								
San Juan Ave - Fair Oaks Blvd to Winding Wy (N)								
Watt Ave - Arden Wy to Cottage Wy								#4687
Alta Arden Expressway - Phase 1	3	Sidewalk gap closures, buffered bike lanes, restriping, traffic signal modifications, pavement rehabilitation and resurfacing.	Michael Dunn-Vecchio	09/24 (A)	Nov-27	Apr-28	Nov-28	\$2,988
Alta Arden Expressway: Howe Ave to Fulton Ave								
Arden Way Complete Streets Project - Phase 1	3	Streetscape bike and pedestrian improvements on Arden Way.	Josh Iniguez	12/23 (C)	May-24	Jul-25	May-26	\$7,428
Arden Way: Morse Ave to Watt Ave								
Arden Way Complete Streets Project Phase 2	3	Streetscape bike and pedestrian improvements on Arden Way.	Dane Coyle	07/22 (A)	Oct-27	Apr-28	Jun-29	\$8,904
Arden Way: Heskett Way to Morse Ave								
Bell Street Safe Routes to School	3	Install bicycle and pedestrian improvements. Sidewalk infill, ADA ramps, school crossings, bicycle lanes, pedestrian signal, timed school zone flashing beacon, traffic signal upgrades and improved street lighting at the intersections.	Dane Coyle	11/23 (A)	Sep-27	Mar-28	Jul-29	\$10,519
Bell Street: Hurley Way to Edison Ave								

Project Name & Locations	Supv. Dist.	Project Description	Project Engineer	Plans Sent to Utilities	Board Approval	Constr Starts	Constr Complete	Contract Amount (\$K)
Bradshaw Rd at Ballinger Dr Traffic Signal	5	Install new traffic signal at Bradshaw Road and Ballinger Dr	James Eslabon	05/25 (A)	Dec-27	Apr-28	Oct-28	\$1,224
<i>Schedule pushed due to anticipated ROW challenges</i>								
<i>Local Funds</i>								
Bradshaw Rd and Elder Creek Rd Improvement Project Intersection of Bradshaw Rd and Elder Creek Rd	5	Intersection widening at the intersection of Bradshaw Rd and Elder Creek Rd	Yinlun Xu	09/25 (B)	Feb-27	Apr-27	Nov-27	\$1,632
<i>Local Funds</i>								
Bradshaw Rd and Gerber Rd Improvement Project Intersection of Bradshaw Rd and Gerber Rd North side of Gerber Rd between Diamond Ranch Rd and Bradshaw Rd	5	Intersection widening at the intersection of Bradshaw Rd and Gerber Rd, widen the north side of Gerber Rd between Diamond Ranch Rd and Bradshaw Rd, box culvert replacement.	David Markowski	09/25 (B)	Dec-27	Apr-28	Oct-28	\$4,214
<i>Local Funds</i>								
Bradshaw & Jackson Intersection Improvements Bradshaw Rd at Jackson Rd	5	Intersection improvements and signal modifications to relieve congestion.	David Markowski	12/22 (B)	Dec-27	Apr-28	Oct-28	\$3,682
<i>Schedule pushed due to coordination delays with Caltrans</i>								
<i>SACOG 2023 M&M; STIP (Federal)</i>								
Bradshaw Road Widening Bradshaw Rd: Kiefer Blvd to Jackson Road/SR-16	5	Widen Bradshaw Road to a six-lane thoroughfare from Kiefer Blvd to Jackson Rd. Modify the traffic signal at Bradshaw Rd and Kiefer Blvd to include an additional through lane in the southbound direction. Improvements include landscaped median, curb, gutter, and sidewalk, and 10' trail.	Gabriel Flores	11/23 (A)	Oct-28	Apr-29	Jul-30	\$8,773
<i>Schedule pushed due to anticipated ROW challenges</i>								
<i>Local Funds</i>								
Bridge Preventive Maintenance Program (BPMP) Kiefer Blvd over Deer Creek and other various locations	1,2,3,4,5	Bridge Preventive Maintenance on various bridges including Methacrylate treatment, joint seal replacement, and/or overlay repair as identified in Caltrans SM&I reports.	Tim Stevens	02/25 (A)	Oct-27	Apr-28	Oct-28	\$1,600
<i>HBP Funds</i>								
Calvine Road Widening Project Calvine Rd: Power Inn Rd to Elk Grove-Florin Rd	5	Widen Calvine Road from 4 to 6 lanes on both sides (City of Elk Grove on south side). Improvements include widening of RR and creek crossing, curb, gutter, and sidewalk, signal modifications, and street lighting.	Anthony Voo	11/25 (A)	Oct-27	Mar-28	Nov-28	\$10,490
<i>Increase in contract amount to reflect expanded scope to include City side.</i>								
<i>Local Funds</i>								
Countdown Pedestrian Head Installation Project Throughout the unincorporated County		Project will provide enhanced pedestrian safety and compliance at signalized intersections with existing pedestrian crossings by installing countdown pedestrian modules. It will consist of 167 signalized intersections.	Don Nguyen	N/A	Sep-25	Apr-26	May-26	\$170
<i>#4691</i>								
<i>State (HSIP)</i>								
Clay Station Road - Hadselville Creek Water Diversion	5	Install water diversions at two creeks on Clay Station Road to allow in-house forces a place to work	Tim Stevens		Jul-26	Sep-26	Oct-26	\$300
Curb, Gutter, and Sidewalk Replacement Project 2025 Countywide	1,2,3,4,5	Replacement of damaged Curb, Gutter and Sidewalk throughout the County.	Daniel Lockett		Jan-26	May-26	Jun-26	\$600
<i>#4680</i>								
<i>Local Funds</i>								

Project Name & Locations	Supv. Dist.	Project Description	Project Engineer	Plans Sent to Utilities	Board Approval	Constr Starts	Constr Complete	Contract Amount (\$K)
Dry Creek Pkwy Phase 2 Multi Use Trail Project	4	New paved Class I Multi-use trail with shoulder, 2 bridges and roadway crossing evaluation.	David Markowski	02/25 (A)	Oct-27	Mar-28	Oct-28	\$7,100
<i>ATP State (Cycle 6)</i>								
Elkhorn Blvd at 28th St. Signal Project	4	Install new traffic signal at the intersection of Elkhorn Blvd and 28th St.	Anthony Voo	03/25 (A)	Dec-27	Apr-28	Oct-28	\$1,150
<i>Update to contract amount based on current unit prices and scope.</i>								
<i>HSIP (Federal)</i>								
Elkhorn Boulevard Complete Streets Project Elkhorn Blvd: Watt Ave to Don Julio Blvd	4	Construct a Class IV separated bikeway, intersection and sidewalk improvements.	Joshua Iniguez	04/25 (B)	Apr-27	Oct-27	Oct-28	\$9,900
<i>Update to contract amount based on current unit prices and scope.</i>								
<i>Note: State ATP, Federal ATP, CDBG</i>								
Elverta Road Improvement Project Elverta Rd: Watt Ave to Dutch Haven Blvd	4	Replace existing two lane bridge at Dry Creek with a six-lane (future) reinforced concrete bridge, replace existing culvert on Elverta Rd. and modify the signal at Elverta Rd and 28th St. The project will widen Elverta Rd. to 4 lanes with landscaped median, and Class II bike lanes.	Gabriel Flores	02/19 (B)	Jan-27	Apr-27	Nov-28	\$16,772
<i>Federal: HBP, STIP, RSTP</i>								
Eschinger Road Intersection Improvements Bruceville Rd to Carroll Rd	5	Widen the intersections of Eschinger Rd at Carroll Rd and Bruceville Rd.	Anthony Voo	03/25 (B)	Nov-26	Mar-27	Jun-27	\$940
<i>Update to contract amount based on current unit prices and scope.</i>								
<i>Schedule pushed due to anticipated ROW delays.</i>								
<i>Local Funds</i>								
Fair Oaks Blvd Bike Pedestrian Mobility Project Phase 2 Fair Oaks Blvd: Howe Ave to Munroe St	3	Create a smart growth corridor with barrier separated bicycle lanes, and improved pedestrian access. Resurface roadway and install landscaping, shade trees, and street lighting. New traffic signals at University Ave/FOB and Fulton Ave/FOB. Signal modifications at Sierra Blvd/FOB.	David Markowski	06/25 (C)	Jan-26	Jul-26	Jul-27	\$10,200
<i>Increase in contract amount based on current unit prices.</i>								
<i>Schedule pushed slightly due to coordination delays with Caltrans #4584</i>								
<i>Federal (CMAQ, RSTP)</i>								
Florin Road Bicycle Pedestrian Improvements Florin Rd: Franklin Blvd to Power Inn Rd	2	Install bike lanes along Florin Road, upgrade traffic signals to accommodate bikes at all intersections, construct associated ADA Improvements, install roadway lighting, and roadway resurfacing along portions of Florin Rd between Franklin Blvd and Power Inn Rd.	Anthony Voo	04/24 (C)	Oct-21	Dec-24	May-26	\$12,684
<i>Teichert Construction - #4526</i>								
<i>Federal (HSIP-C8, RSTP), CDBG, ARPA, Local Funds</i>								
Folsom Blvd Complete Streets Improvements Phase 2 Folsom Blvd: Starfire Dr to Mayhew Rd	3,5	Install bike lanes, sidewalks, street lights, landscaping, fencing, ADA ramp and signal upgrades at La Riviera Dr, Tiber Dr, and Mayhew Rd.	Anthony Voo	08/21 (A)	Dec-26	Mar-27	Nov-27	\$6,000
<i>Local Funds</i>								
Franklin Blvd Bridge Replacement at Lost Slough Franklin Blvd at Lost Slough	5	Replace bridge at Lost Slough on Franklin Blvd.	James Eslabon Conсор Eng	03/23 (C)	Sep-24	May-25	Apr-26	\$10,246
<i>Viking Construction - #4391</i>								
<i>Federal (HBP)</i>								
Freeport Bridge Deck Repair 24C0001 Freeport Bridge over Sacramento River	2	Maintenance Project to repair damaged bridge deck welds	Tim Stevens		Jan-26	Apr-26	Jun-26	\$300
<i>Local Funds</i>								

Project Name & Locations	Supv. Dist.	Project Description	Project Engineer	Plans Sent to Utilities	Board Approval	Constr Starts	Constr Complete	Contract Amount (\$K)
Freeport Delta Monument Signs Project Freeport Blvd: South of Cosumnes River Blvd	5	Easement acquisitions, final design, fabrication and construction of gateway monuments and interpretative sign on Freeport Blvd.	Hussein Abdu		Sep-26	Jan-27	Jun-27	\$296
<i>State Funds, Road Fund (Cost Share)</i>								
Fruitridge Sidewalk Project Phase 2 and 3 Various locations in Fruitridge neighborhoods	1	Replacement of damaged gutter and sidewalk in Fruitridge area	Brandon Lew		Sep-25	Feb-26	Mar-26	\$330
<i>#4660</i>								
<i>Federal Funds (CDBG)</i>								
Gerber Road Traffic Signals Project Gerber Rd at Passalis Ln Gerber Rd at Excelsior Rd	2,5	Install new traffic signals at Gerber Rd at Passalis Lane and Gerber Rd at Excelsior Rd.	James Eslabon	03/26 (B)	May-27	Aug-27	Jan-28	\$4,388
<i>Update to schedule</i>								
<i>Local Funds</i>								
Greenback Lane Improvements and Undergrounding Greenback Ln: Chestnut Ave to Folsom City Limits	4	Install Class II Bike Lanes, infill sidewalk and separated sidewalk, ADA upgrades: curb ramps, traffic signal modifications with bicycle detection, bus stop and transit access improvements, pavement repair, and landscape/streetscape enhancements including raised/landscaped medians. Includes signalization of the Chestnut Avenue/ Greenback Lane intersection and undergrounding of overhead utility lines.		12/20 (A)	Nov-27	Apr-28	Oct-29	\$10,055
<i>Update to contract amount based on current unit prices</i>								
<i>#4560</i>								
<i>Note: Local funds</i>								
Green Tree Dr., Franklin Blvd, and East Pkwy Green Tree Dr 300' east of Franklin Blvd Franklin Blvd between Florin Rd and Green Tree Dr East Pkwy from Florin Rd to 400' south of Florin Rd	2	Install street lights on Green Tree Dr just east of Franklin Blvd and on Franklin Blvd between Green Tree Dr and Florin Rd; install sidewalk on the west side of East Pkwy from Florin Rd to 400' south of Florin Rd. County Neighborhood Improvement Initiative	Anthony Voo	05/25 (C)	May-25	Sep-25	Feb-26	\$305
<i>Project is complete and will be removed from the July 2026 PML</i>								
<i>Martin General Engineering, Inc. - #4665</i>								
<i>Local Funds</i>								
Hazel Ave at US Highway 50 Interchange - Segment 1 Hazel Ave at US Highway 50 Interchange	3	Reconstruct portions of the US 50 Hazel Ave Interchange and improvements to eastbound US 50, including ramp modifications at Aerojet Rd and Folsom Blvd off ramps. Includes a grade separated crossing of the Gold Line Light Rail system and Folsom Blvd, multi-use path from American River Parkway to south of US 50. First segment of larger project described above.	Spencer Ord	12/25 (B)	Jun-26	Feb-27	Oct-28	\$28,500
<i>Schedule updated to reflect current funding deadlines.</i>								
<i>State, Local</i>								
Madison Ave Fair Oaks Blvd to Hazel Ave Madison Ave: Sunrise Blvd to Hazel Ave	3	Capacity and complete street improvements on Madison Ave between Sunrise Blvd and Hazel Ave in the Fair Oaks, Citrus Heights, and Orangevale areas.	David Markowski	01/20 (A)	Nov-29	Apr-30	Dec-31	\$18,039
<i>Federal (CMAQ, RSTP)</i>								
Meister Way Improvement Project Meister Wy: Bear Paw Dr to Lone Tree Rd	1	Reconstruct Meister Way to a two-lane arterial. Project includes installation of traffic signals at Metro Air Parkway, Badiee Drive, and Lone Tree Road and will also include sewer, water, and storm drain improvements.	Gabriel Flores	11/24 (C)	Jun-25	Apr-26	Oct-26	\$8,319
<i>DeSilva Gates Construction - #4656</i>								
<i>Note: Local Funds, MAP</i>								
Metro Air Parkway Ramp Signalization Project Metro Air Pkwy at I-5 off-ramps	1	Install signals at the southbound and northbound off-ramps at the I-5/Metro Air Pkwy Interchange. Slurry and restripe.	David Markowski	01/26 (C)	Jun-25	Jul-26	Apr-27	\$1,591
<i>Local Funds, MAP</i>								

Project Name & Locations	Supv. Dist.	Project Description	Project Engineer	Plans Sent to Utilities	Board Approval	Constr Starts	Constr Complete	Contract Amount (\$K)
Michigan Bar Rd/ Cosumnes River Bridge Replacement Michigan Bar Rd: North of SR 16 at Consumnes River	4	Replacement of an existing modular concrete panel deck on modular steel box deck trusses and steel girders bridge w/new two-lane road concrete slab bridge. Approx. 1 mile n/o SR16. Bridge No 24C0056	James Eslabon Dewberry	04/17 (B) <i>Schedule pushed due to anticipated ROW delays.</i>	Aug-28	May-29	Nov-29	\$4,950 #4416
<i>Note: Federal Funding (HBP)</i>								
Neighborhood Traffic Management Project 2026 1) Mendocino Blvd (26th Ave - Sierra Vista Ave) 2) Bothwell Dr (Vintage Park Dr east - Heathfield Way) 3) Westray Dr (Waterman Rd - Montevina Dr) 4) California Ave (Fair Oaks Blvd - Sutter Ave) 5) Esteem Dr (Antelope Dr - Monogram Dr) 6) Forestwood Dr (Diablo Dr - Hedgewood Dr) 7) Karm Way (Andrea Blvd - Diablo Dr) 8) Saint James Dr (Oleander Dr - Dewey Dr) 9) Sutter Ave (Fair Oaks Blvd - California Ave) 10) Wyda Way (Wright St - Alta Arden Expy) 11) 18th St (Elkhorn Blvd - I St) 12) 20th St (Elkhorn Blvd - Q St) 13) Channing Dr (Watt Ave - Thomas Dr) 14) U St (32nd St - 34th St) 15) Eisenhower Dr (Rosemont Dr - Huntsman Dr) 16) River Rd (Walnut Grove Rd - Depot Ln) 17) Reese Rd (Mcnie Ave - 2000 ft south of Mcnie Ave)	1,2,3,4,5	Install speed bumps, speed tables, and corresponding signage at various locations within the County.	Noel Pacheco	N/A	Feb-26	Jul-26	Oct-26	\$410
New Hope Road Bridge Replacement at Grizzly Slough New Hope Rd: Grizzly Slough to half a mile n/o the San Joaquin County Line	5	Replacement of an existing two-lane road concrete bridge with a new two-lane bridge on New Hope Road at Grizzly Slough waterway and about half a mile n/o the San Joaquin County Line.	Michael Dunne-Vecchio Mark Thomas	10/25 (C)	Dec-25	Apr-26	Oct-26	\$4,536 Viking Construction - #4664 Federal (HBP)
North Watt Ave Area Pedestrian Improvements Winona Way: Watt Ave to Roseville Rd	3	Install sidewalk infill and street lights on Winona Way.	Dane Coyle	05/25 (C) <i>Project is complete and will be removed from the July 2026 PML</i>	May-25	Sep-25	Dec-25	\$446 Central Valley Eng & Asphalt - #4671 Federal (CDBG)
Oakdale Elementary, College Oak Dr Myrtle Ave at Polk St College Oak Dr between Myrtle Ave and Orange Grove Ave	3	Install accessible corner ramp/sidewalk at Polk St and Myrtle Ave; install street lights on College Oak Dr. County's Neighborhood Improvement Initiative	James Eslabon	01/25 (A) <i>Schedule pushed due to anticipated ROW delays.</i>	Mar-27	Jul-27	Nov-27	\$520 Local Funds
Power Line Road Improvements - Phase 2/ Elverta Rd Elverta Rd: E/o Power Line Rd to 1400' w/o Metro Air Pkwy	1	Widen Powerline Rd and Elverta Rd to add a center turn lane and associated drainage improvements. Waterline will also be installed.	David Markowski	07/25 (B) <i>Schedule pushed due to anticipated ROW delays.</i>	Nov-26	Apr-27	Aug-27	\$6,400 Local funds, MAP

Project Name & Locations	Supv. Dist.	Project Description	Project Engineer	Plans Sent to Utilities	Board Approval	Constr Starts	Constr Complete	Contract Amount (\$K)
Retro-reflective Signal Backplate Installation Project Throughout the unincorporated County		Project will provide enhanced visibility of traffic signal indications by upgrading signal backplates to include retroreflective yellow borders. It will consist of 512 signalized intersections.	Don Nguyen		Apr-26	Jun-26	Sep-26	\$790
<i>State (HSIP)</i>								
Sacramento Northern Bike Trail Extension Project Elverta Park & Ride lot north to 1/4 mile n/o the Sacramento County/Placer County Border	4	PA&ED and Public Outreach including Placer County for a 1.5 miles extension of the existing class 1 (bike) trail.	Anthony Voo	09/25 (A)				
<i>Federal Carbon Reduction Program(CRP) Grant; construction funding TBD</i>								
Skyking Road Extension & Phelan Drive Project	1	This project will extend skyking Road from Metro Air Parkway to Phelan Dr. The extension of Skyking Rd will be a two-lane collector.	Gabriel Flores	12/25 (C)	Jan-26	May-26	Oct-26	\$2,365
<i>Update to contract amount based on current unit prices</i>								
<i>Local funds</i>								
South Sacramento Sidewalk Gap Closure Project Power Inn Rd: Stevenson Ave to about 630 feet south	2	Install sidewalk at various locations in South Sacramento	Michael Dunne-Vecchio	06/25 (B)	Dec-26	Apr-27	Oct-27	\$3,455
Power Inn Rd: at the intersection of Elsie Ave								
Stevenson Ave: Cottonwood Ln to 975 feet west								
Cottonwood Ln: Elsie Avenue and Stevenson Avenue								
<i>Update to contract amount based on current unit prices</i>								
<i>Federal (RSTP, STIP)</i>								
South Watt Ave Improvements Florin Rd to SR16 Florin Rd to Jackson Rd (SR-16)	1	Widen South Watt Ave from 2 lanes to 4 lanes, including railroad crossing and bridge at Morrison Creek.	Keith Gotwalt	04/24 (C)	Jul-24	Apr-25	May-27	\$59,520
<i>Teichert Construction - #4627</i>								
<i>State (STIP, SB 1-C: LPP Competitive)</i>								
South Watt Ave Improvements SR16 to Kiefer Blvd Jackson Rd (SR-16) to Kiefer Blvd	1	Widen South Watt Ave from 5 lanes to 6 lanes with sidewalks and signal modifications.	Yinlun Xu	11/25 (A)	Feb-28	Apr-28	Dec-28	\$2,800
<i>Local Funds</i>								
Stockton Blvd Complete Streets Project Mack Rd to Florin Rd	2	Construct Class IV bicycle lanes or a two-way cycle track on one side of Stockton Blvd, sidewalk infill, signalization of one intersection, slurry seal and restriping of entire roadway/bikeway.	Michael Dunne-Vecchio	10/24 (A)	Dec-28	Jul-29	Apr-30	\$10,100
<i>State (ATP)</i>								
Sunrise Boulevard Bridge over American River	3,5	BIP Feasibility Study and HBP Scour Countermeasures	Tim Stevens		Jan-31	Jul-31	Oct-31	\$4,500
Sunrise Boulevard Wall Replacement Project Sunrise Blvd between Sunset Ave and Wildridge Dr	3	Replace approximately 600 feet of the leaning wall along the west side of Sunrise Blvd.	Spencer Ord	08/24 (A)	May-26	Aug-26	Nov-26	\$1,500
<i>Schedule pushed slightly due to right-of-way acquisition delays.</i>								
<i>Local Funds</i>								
Sutter Slough Bridge Repair Project Sutter Slough Bridge over Sutter Slough	3	Repair damaged truss members from vehicle collision. Bridge No. 24C0011	Tim Stevens	N/A	Apr-25	Aug-25	Oct-25	\$900
<i>NMI Industrial Holdings, Inc. - #4672</i>								
Twin Cities Road Bridge Replacement Twin Cities Rd Bridge over Snodgrass Slough	5	Remove the existing movable swing bridge over Snodgrass Slough at Twin Cities Road and replace it with a reinforced concrete bridge.	Jenny Singh Dokken Eng.	10/21 (C)	Dec-27	May-28	Oct-30	\$16,084
<i>Schedule pushed due to right-of-way acquisition delays with USFW.</i>								
<i>Federal (HBP)</i>								

Project Name & Locations	Supv. Dist.	Project Description	Project Engineer	Plans Sent to Utilities	Board Approval	Constr Starts	Constr Complete	Contract Amount (\$K)
Tyler Island Bridge Replacement Project Tyler Island Rd Bridge over Georgiana Slough	5	Replace moveable bridge over Georgiana Slough or BPMP pending Caltrans required soil analysis study.	Tim Stevens		Oct-29	Apr-30	Oct-30	\$9,200
<i>Pending approval - Federal (HBP)</i>								
Walmart Bridge Repairs Walmart Rd: Dillard Rd and Davis Rd	5	Replace existing 2-lane wooden bridge with new 2-lane concrete bridge.	Tim Stevens		Dec-26	May-27	Oct-27	\$500
Walnut Grove Bridge over Sacramento River BPMP Walnut Grove Bridge over Sacramento River: Hwy 160 to River Rd Bridge Preventive Maintenance Project	5	Preventive Maintenance Project, Bridge No. 24C0005	Tim Stevens		Oct-28	Apr-29	Oct-29	\$5,600
<i>Schedule TBD</i>								
<i>Project name updated from Walnut Grove Bridge over Sacramento BMP</i>								
Walnut Grove over Mokelumne River Bridge Thornton Rd. Bridge over Mokelumne River Bridge No. 29C0131	5	Replace the existing bridge with new movable bridge to accommodate 2 vehicle lanes and shoulder and meet safety and design standards.	Tim Stevens			Jul-29		\$35,000
<i>San Joaquin County is lead agency on this project</i>								
<i>Project name updated from Walnut Grove Thornton Road Bridge Replacement Project</i>								
Waterman Road CCTC Crossing	5	Install a new at-grade crossing on Waterman Road at the existing CCTC Railroad Crossing	David Markowski	08/22 (A)	Oct-26	Apr-27	Nov-27	\$2,766
Watt Ave Complete Street Improvements Project Watt Ave: I-80 to Roseville Rd	3	Widen Watt Ave. to accommodate buffered bike lanes, streetscaping, landscaped median, upgraded traffic signals, separated sidewalks, street lighting, overlay.	Keith Gotwalt	02/24 (C)	Jul-24	Apr-25	Nov-26	\$13,535
<i>Project is complete and will be removed from the July 2026 PML</i>								
<i>Central Valley Eng & Asphalt - #4607</i>								
<i>Federal (CMAQ, RSTP, CDBG, SB 1-SCCP)</i>								
Whitney Avenue Road Diet & Multi Modal Improvement Project	3	Create a multi-modal corridor with separated bicycle lanes, improved pedestrian access, resurfaced roadway. Traffic signal modifications at Whitney/Watt Ave, Whitney Ave/Becerra way, Whitney Ave/Norris Ave, Whitney Ave/Eastern Ave, and Whitney Ave Foster way.	Dane Coyle		Nov-29	Apr-30	Oct-30	\$5,400
<i>State ATP</i>								
Winter Storm 2022-2023 Alta Mesa Culvert Alta Mesa Rd south of Boessow Road Alta Mesa Culvert	5	Replace culvert under Alta Mesa Road damaged by storm.	Tim Stevens	08/25 (C)	Jul-25	May-26	Jul-26	\$370
<i>#4684</i>								
Winter Storm 2022-2023 Lone Road Lone Road South of Jackson Road	5	Replace culvert under for Lone Road damaged by storm.	Tim Stevens		May-26	Aug-26	Oct-26	\$450
<i>Federal (ER)</i>								
Wyda Way Sidewalk Gap Closure Wyda Way: Jerron PI to Markston Rd	3	Sidewalk infill, accessible ramps, street lights, drainage improvements, pavement repair.	Yinlun Xu	03/26 (C)	May-26	Aug-26	Nov-26	\$1,224
<i>Contract amount updated to reflect current scope. Schedule pushed due to ROW delays.</i>								
<i>Federal (CDBG), local funds</i>								